

# Before Setting off Checklist Guide

- Has the caravan been correctly connected to the car?
- Are the Jockey wheel and stabilizer legs retracted?
- Is the ball weight correct?
- Is the breakaway cable correctly attached?
- Is the lighting plug correctly inserted and secure?
- Have the wheel chocks & levelers been removed and correctly stowed away?
- Do all the indicator lights on the caravan and car work?
- Are all the doors, external lockers, windows and hatches securely closed?
- Are the tables securely stowed?
- Has the caravan been loaded correctly?
- Is the load inside the caravan secured?
- Are the gas cylinders secured and turned off?
- Are the outside mirrors on the towing vehicle securely fitted and set correctly?
- Has the pressure of all the caravan tyres been checked?
- Has the spare wheel been checked?
- Is the TV aerial down and secure?
- Has the Television been stowed correctly.
- Has the key been removed from the door?
- Is the fridge door secure?
- Have any pictures or paintings been stowed for transit?
- Is the stone shield secure?
- Has the step been stowed or retracted?
- Has the air pressure in the vehicles tyres been checked?
- Have you left anything behind - Check after moving off site but before leaving.
- Have you returned any ablution keys?